Accuracy of scaled GRACE terrestrial water storage estimates

F. W. Landerer

Jet Propulsion Laboratory / California Institute of Technology, Pasadena,

CA, U.S.A.

S. C. Swenson

NCAR - Climate and Global Dynamics Division, CO, U.S.A.

—————

F. W. Landerer (landerer@jpl.nasa.gov)

Abstract.   We assess the accuracy of global gridded terrestrial water storage (TWS) estimates derived from temporal gravity field variations observed by the GRACE satellites. The TWS data set has been corrected for signal modification due to filtering and truncation. Simulations of terrestrial water storage variations from land-hydrology models are used to infer relationships between regional time series representing different spatial scales. These relationships, which are independent of the actual GRACE data, are used to extrapolate the GRACE TWS estimates from their effective spatial resolution (length scales of a few hundred km) to finer spatial scales (approximately 100 km). Gridded, scaled data like these enable users who lack expertise in processing and filtering the standard GRACE spherical harmonic geopotential coefficients to estimate time series of TWS over arbitrarily shaped regions. In addition, we provide gridded fields of leakage and GRACE measurement errors that allow users to rigorously estimate the associated regional TWS uncertainties. These fields are available for download from the GRACE project website (http://grace.jpl.nasa.gov).

Three scaling relationships are examined: 1) a single gain factor based on regionally averaged time series, 2) spatially distributed (i.e. gridded) gain factors based on time series at each grid point, and 3) gridded gain factors estimated as a function of temporal frequency. While regional gain factors (1) have typically been used in previously published studies, we find that comparable accuracies can be obtained from scaled time series based on gridded gain factors (2). In regions where different temporal modes of TWS variabil-

ity have significantly different spatial scales, gain factors based on the first

two methods may reduce the accuracy of the scaled time series. In these cases,

gain factors estimated separately as a function of frequency may be neces-

sary to achieve accurate results.

1. Introduction

The Gravity Recovery and Climate Experiment (GRACE) observes temporal variations of Earth's gravitational potential. After atmospheric and oceanic effects are accounted for, the remaining signal on monthly to interannual time scales is mostly related to variations of terrestrial water storage (TWS). Estimates of water storage variations suffer from signal degradation due to measurement errors and noise, which are manifested as both random errors that increase as a function of spherical harmonic spectral degree [*Wahr et al.*, 2006], and systematic errors that are correlated within a particular spectral order [*Swenson and Wahr*, 2006]. Several filtering approaches currently exist to either damp or isolate and remove these errors. In practice, however, filters also modify the true geophysical signal of interest. Filter design focuses on this trade-off, and attempts to minimize signal loss while maximizing noise reduction [*Swenson and Wahr*, 2011].

Because the spatial resolution of filtered GRACE data is typically more coarse than that of other hydrological data sets, it is necessary to reconcile differences in spatial scale between data sets before an equitable analysis can be performed. When the signal modification resulting from filtering the GRACE data is not accounted for, apparent differences between the TWS estimates will erroneously be attributed to either shortcomings in the observations or model data, when these differences are in fact due to a mismatch in spatial scales [*Tang et al.*, 2010].

A straightforward way to reconcile spatial resolution discrepancies is to filter each data set in the same way. This approach has been used previously when validating satellite-based estimates of winter precipitation [*Swenson*, 2010] and global land-hydrology models

[e.g., *Schmidt et al.*, 2006]. An alternate approach is to scale the GRACE data to account for the effect of the filter on the signal. A number of studies [e.g., *Swenson and Wahr*, 2007; *Rodell et al.*, 2004; *Klees et al.*, 2007; *Landerer et al.*, 2010] have estimated the signal attenuation in basin-averaged time series and applied a gain factor to the GRACE observations. If not restored, signal attenuation will reduce the ability to close the regional water balance, or when the water budget is used to estimate one component as a residual, signal attenuation becomes an error in the residual. As it is cumbersome for users of GRACE data to estimate the signal degradation via the described route, hydrological research would greatly benefit from gridded GRACE data that can be used as an independent, stand-alone and unambiguous data set for hydrology applications without a geodesist's assistance [*Rodell et al.*, 2010]. This would allow users to average gridded GRACE data over user-defined regions, where the signal attenuation has already been corrected for as part of the GRACE post-processing, and the errors and uncertainties of a regional average can also be computed from gridded data.

In this paper, we describe the scaling technique used to restore some of the signal loss in regionally averaged time series due to filtering and truncation of GRACE TWS observations, and apply it to regions consisting of 1 by 1 degree grid cells. The resulting data set is publicly available via the Jet Propulsion Laboratory's TELLUS website (http://grace.jpl.nasa.gov). We then compare the accuracy of regional time series scaled using a bulk gain factor to a regional time series computed using the gridded data set to which distributed gain factors have been applied. Next, we compare the effectiveness of single gain factors relative to frequency-dependent gain factors for a scenario where seasonally varying TWS signals have significantly different spatial patterns then secularly

varying TWS signals. We then discuss the limitations of this scaling approach, which should help users of gridded GRACE TWS data to realize the full potential of this data set while being aware of the uncertainties. The goal of this approach is to simplify the use of GRACE TWS observations for hydrological applications, and to allow for a rigorous quantification of leakage and measurement errors.

2. A Gridded GRACE Dataset

The standard products of the GRACE Project are sets of spherical harmonic coefficients describing the monthly variations in Earth's gravity field, which can be inverted to estimate changes in mass at the surface [*Wahr et al.*, 1998]. After filtering to reduce the presence of measurement errors, the data can be gridded, i.e. converted from spectral coordinates to geographical coordinates, in order to create maps of surface mass variations.

The GRACE filter used in this study consists of two parts. The first filter is designed to remove systematic errors that are characterized by correlations between certain spherical harmonic coefficients; these errors are manifested as North-South oriented 'stripes' in maps of GRACE TWS [*Swenson and Wahr*, 2006, Fig. 1]. The second filter is a Gaussian averaging filter with a half-width of 300 km that reduces random errors in higher degree spherical harmonic coefficients not removed by "de-striping" [*Wahr et al.*, 1998, 2006]. The Gaussian filter is a smoothing operation and reduces the spatial resolution of GRACE observations by damping the higher degree coefficients.

Another feature of GRACE data is that the gravity field solutions are typically truncated at a spectral degree $l_{max} \leq 60$. Thus, signals having spatial variability with spatial scales finer than a few hundred km are not resolved by GRACE (e.g., $l_{max} = 60$ represents

a wavelength of approximately 330 km). This form of signal loss can be thought of as resulting from the application of a spectral low-pass filter.

The errors in the filtered data are estimated following the method described in *Wahr et al.* [2006]. The top panel of Fig. 1 shows the root-mean-square variability in the filtered GRACE TWS data, gridded at 1 degree spatial resolution. The bottom panel shows our estimate of the RMS measurement error, which exhibits a zonally banded pattern, with maximum errors of about 36 mm water-equivalent height at lower latitudes; pole-ward, the error decreases to less than 15 mm.

3. Signal Attenuation from Filtering

All water storage observations from GRACE represent average values, in both space and time. Temporally, GRACE data are approximately monthly averaged quantities. Due to truncation and filtering in the spectral domain, GRACE data are also spatially averaged, with spatially varying weights. This results in a time series that differs from the true, i.e. uniformly weighted, time series; this difference is often referred to as "leakage". The leakage error depends on the filtering process, as well as the characteristics of the signal.

The effects of the successive filter operations on the GRACE observations are shown in Fig. 2. In the top left panel, the RMS variation of the original GRACE data are shown. Large amplitudes and prominent stripe-like features can be observed. After filtering (Fig. 2, bottom left panel; note different scale), the presence of these features is largely absent, indicating the effectiveness of the filtering process in reducing errors. However, the filters' effects on the actual signal cannot be ascertained from GRACE data alone. Instead, simulations based on realistic TWS models can be used [*Swenson et al.*, 2003; *Seo and Wilson*, 2005].

To obtain quantitative estimates of signal attenuation and leakage error that arise from the application of these GRACE post-processing filters, we use synthetic monthly TWS anomalies form Jan-2003 to Dec-2009 simulated by the NOAH land model, running within the Global Land-Data Assimilation System (GLDAS-NOAH, [*Rodell et al.*, 2004]). GLDAS-NOAH does not explicitly simulate groundwater and surface water, and we exclude TWS variations of glaciers and ice sheets, as these are either not included or unrealistic due to missing model physics. Methods to correct for signal attenuation for Greenland and Antarctica can be found in, e.g., *Velicogna* [2009] and *Chen et al.* [2009]. In order to create a synthetic TWS data set, the model data are first converted to spherical harmonic coefficients, and the two-step GRACE filter is applied. Next, the coefficients are re-mapped to the original 1×1 latitude/longitude grid [*Wahr et al.*, 1998] to quantify the signal attenuation.

The original GLDAS-NOAH model data (Fig. 2, top right panel) at 1×1 degree resolution is taken as the reference, relative to which the filtering effects are evaluated. When applying GRACE filters to the model data (Fig. 2, bottom right panel), an implicit filtering step consists of truncating the model data at a spectral degree and order of 60 (or less), since most GRACE observations are only provided at that resolution. This truncation alone effectively reduces the spatial resolution from ~110 km to ~330 km at the Equator. Geophysical signals with a prominent North-South orientation are further attenuated by the de-striping filter, and smoothing the truncated, de-striped data with a Gaussian averaging radius of 300 km also reduces signal variance. Signals along coastlines are particularly prone to signal attenuation because the filtering process removes short wavelength features. Therefore, grid points close to the ocean represent averages that

include the typically much smaller ocean signals, resulting in strong reductions of TWS signal amplitude (e.g., along the US West-Coast). Only very few regions exist where the ocean signals are large enough to potentially leak onto land and interfere with terrestrial water storage signals (e.g., Gulf of Carpentaria North of Australia). Since an ocean model is removed in the GRACE processing, ocean-to-land leakage effects are already significantly reduced.

4. Restoring Signal Attenuation

4.1. Basin-Scale Gain Factors

We quantify leakage error with the root-mean-square difference (RMSD) between the unfiltered and the filtered monthly mean GLDAS-NOAH water storage estimates. In order to reduce this leakage error, we derive a gain factor k by minimizing the misfit between the unfiltered, true (ΔS_T) and filtered (ΔS_F) storage time series through a simple least-squares regression:

$$M = \sum (\Delta S_T - k\Delta S_F)^2, \tag{1}$$

where the summation is over the 84 months of GLDAS-NOAH data used here. Several studies have used this approach to restore TWS signals over hydrological drainage basins [e.g., *Famiglietti et al.*, 2011; *Swenson and Wahr*, 2007; *Klees et al.*, 2007; *Chen et al.*, 2007].

As an illustrative example, we use Eq. 1 to derive the gain factor for the basin-mean monthly TWS in the Columbia River basin in the North-West US (Fig. 3). Applying the GRACE filters to GLDAS-NOAH leads to a significant leakage error. A gain factor of 1.44, calculated from Eq. 1, reduces the variance of the leakage error by nearly 85%. When the

gain factor as determined from GLDAS-NOAH is applied to actual GRACE observations, it becomes evident that GLDAS-NOAH underestimates seasonal TWS variations in the Columbia River basin (Fig. 3c), likely due to missing groundwater and river storage components in the present GLDAS-NOAH version (M. Rodell, personal communication). This example also underscores one important aspect of the scaling approach: it does not seek to match GRACE measurements to synthetic model amplitudes, but uses the synthetic model patterns to determine relative signal attenuation based on the ratio of true and filtered signal amplitudes.

Table 1 summarizes the filter parameter-dependent basin-scale gain factors (k_b, second column) for river basins of various drainage areas and locations. Gain factors for basins having large areas are typically close to 1, while smaller basins have larger gain factors. The third column of table 1 lists the initial leakage error (E_b^l), while the fourth column shows the residual leakage error (E_{b,k_b}^l) present after the gain factor is applied to the filtered time series. Comparing E_b^l and E_{b,k_b}^l shows that significant reductions in leakage error variance can be obtained after the application of the gain factor.

4.2. Grid-point Gain Factors

Previous studies [e.g., *Famiglietti et al.*, 2011; *Swenson and Wahr*, 2007; *Klees et al.*, 2007; *Chen et al.*, 2007] have used a scaling approach, computing gain factors for specific regions. To create a global, gridded data set of GRACE TWS observations that can be averaged over arbitrary regions, we apply the scaling procedure to all land points on a 1×1 degree grid. This results in map of gain factors k_g (Fig. 4), that, when applied to the filtered data, restores a significant portion of the signal attenuation. As discussed in more detail below, applying the gain factors first and then averaging leads to regional averages

that are comparable to applying a single gain factor to an unscaled regional average (see also Fig. 3 for the Columbia River as an example).

The gridded gain factors shown in Fig. 4 are generally close to 1, indicating that signal damping is weak over the majority of interior land points. Along coastlines, gain factors significantly larger than 1 are required due to signal interference with the much weaker ocean signal. Areas of low TWS variability (e.g., Northern Africa) are susceptible to leakage errors from larger signals of surrounding regions. In these locations, gain factors less than 1 are then needed to reduce the signal amplification. As filtering may not only change the amplitude, but also change the shape of the signal through interference with out-of-phase signals from surrounding regions, it is instructive to examine the grid-point correlation between the filtered and unfiltered model data (Fig. 5). Correlation values close to 1 indicate that the shape (mostly dominated by seasonal variations) is not strongly affected by the filter, whereas lower correlation values indicate that the spatial averaging caused by the GRACE filter has changed the shape of the signal. This typically occurs where strong gradients in the phase of the TWS signal exist, such as transitions between mountains and plains. In those areas, the spatial decorrelation length is often much shorter than what GRACE can resolve, and therefore signal leakage and interference are strong. The linear scaling approach (Eq. 1) is less effective at restoring the signals in those cases.

4.3. Gridded Uncertainty Estimates

A previously estimated GRACE measurement error [*Wahr et al.*, 2006] did not account for the leakage error from the TWS signals. Fig. 6 shows new estimates of the GRACE measurement error (top) and leakage (middle) error for the gridded GRACE TWS data

set. The measurement errors are the result of multiplying the filtered GRACE measurement error map (Fig. 1) by the grid-point gain factor map (Fig. 4).

At each grid-point, the leakage error estimate has been multiplied by the ratio of the RMS-variabilities of the filtered GRACE and GLDAS-NOAH time series:

$$E_g^l = \text{RMS}(\Delta S_T - k\Delta S_F)\frac{\text{RMS}_{GRACE}}{\text{RMS}_{model}}, \tag{2}$$

with S_T and $k\Delta S_F$ as defined in Eq. 1. The reason for this is that in some cases there is a significant discrepancy between the amplitudes of the GRACE and modeled TWS signals. The total error at each grid point is then obtained by summing leakage and measurement errors in quadrature.

Globally, the application of the gain factors considerably reduces leakage errors. Fig. 7 shows a histogram of the leakage error for the gridded TWS estimates before (blue line) and after (black line) scaling. The total area of grid-points having leakage errors greater than about 5 cm is significantly reduced, leading to a more sharply peaked histogram with more areas having leakage errors in the 2 to 3 cm range. In particular, signals along coastal areas are much better recovered.

The error components shown in Fig. 6 reflect the expected uncertainty in the time series of each individual grid-point. However, the errors in the gridded data are spatially correlated, so the actual error in a regional average time series cannot be obtained by simply averaging the variances from all points within a given region. To obtain a more accurate uncertainty estimate, we introduce an approximation for the error co-variance that is a function of the distance between grid-points. A Gaussian window is used, whose half-width is specified by a parameter d_0 representing the distance at which the function has decreased to half its maximum value. The co-variance between two points x_i and x_j

is then given by

$$Cov(x_i, x_j) = \sigma_i \; \sigma_j \; exp(\frac{-d_{ij}^2}{2d_0^2}),$$

(3)

where σ_i and σ_j are the standard deviations of the uncertainty estimates for grid points i and j, $exp(...)$ is the correlation, d_{ij} is the distance between between grid points, and d_0 is a de-correlation length-scale. The error variance of a regional mean TWS estimate then becomes

$$var = \sum_{i=1}^{N} \sum_{j=1}^{N} w_i \; w_j \; Cov(x_i, x_j),$$

(4)

where w_i is the area weight at each grid point in the basin. The values of d_0 were chosen so that the error budget obtained using the gridded data set matched the budget obtained when computing the regional average TWS time series directly; the area weights w_i simplify to 1/(number of grid points) if one assumes equal contribution from each pixel to the basin mean TWS. For the present choice of filter parameters, we used $d_0^m = 300$km for the measurement errors, and $d_0^l = 100$km for the leakage errors. We determined these values by comparing the error budgets based on basin- and gridpoint-scaled time series for a large number of river basins.

Column 5 in Table 1 shows the residual leakage error (E_g^l) when basin-averaged time series are computed using the gridded gain factors, applied to the GRACE TWS data set. Using these grid-point gain factors k_g, most basin averages have a similar reduction in RMSD relative to the unscaled estimates as the basin-scale gain factors (column 4), typically agreeing to within 20 % or less. This level of agreement can also be seen in the basin-scale (column 6) and gridpoint (column 7) measurement error estimates. Total error estimates, obtained by summing measurement and leakage errors in quadrature, are

shown in columns 8 and 9. Time series for large river basins have RMS-uncertainties that are generally less than 2 cm, while smaller basins have RMS uncertainties around 3 to 4 cm.

An additional amount of uncertainty may arise from uncertainties of the model-based gain factors themselves. The gain factors shown in Fig. 4 are based on GLDAS-NOAH. We evaluated the accuracy of the gain factors by deriving gain factors for the Community Land Model (CLM4) hydrology model [*Oleson et al.*, 2008], and applied the CLM4-based gain factors to the filtered GLDAS-NOAH data. The heterogeneous amplitude reconstructions (e.g., GLDAS-NOAH with CLM4 derived gain factors), yield residual leakage errors that are similar to the homogeneous amplitude reconstruction (e.g., GLDAS-NOAH with GLDAS-NOAH derived gain factors) when averaged over the basins in Tab. 1. The differences in the residual leakage errors for different gridded gain factors are similar to the error differences between basin-scaled and grid-point scaled basin averages. Out of the 46 basins in Tab. 1, the residual leakage error for 24 basins agrees to within 10%, and 40 basins have residual leakage errors that agree to within 25%. For very small basins that cover only a few grid points (e.g., in our sample the Cunene), the residual leakage errors may increase by up to 70%.

As a general rule for the application of gain factors, it must be kept in mind that the estimates of TWS towards the smallest spatial scales can potentially be biased towards the hydrology model on which the gain factors are based upon. Although a user may use the time series of a single pixel (with its possibly large uncertainty), the motivation for the distributed gain factor data is to allow the user to create time series for arbitrarily-shaped regions. As the size of the averaging region increases, the errors generally decrease.

4.4. Modes of temporal TWS variability with different spatial scales

The approach in Eq. 1 to estimate gain factors by minimizing the misfit of the entire time series with a single gain factor lumps together month-to-month variability, seasonal signals, and long-term trends. This issue of different temporal scales concerns both the grid-point and the basin-scaling techniques. When the TWS signal contains different modes of temporal variability that have different spatial patterns, a single gain factor may not yield accurate results. *Chen et al.* [2007] found slightly different attenuation effects for annual and semi-annual components for several large river basins, but the differences were relatively minor for small smoothing radii as used here (300 km). Moreover, the semi-annual TWS amplitudes are generally much smaller than the annual amplitudes (in GLDAS-NOAH and in GRACE), so that the impact of scaling the two components separately was further reduced. Over river basins larger than about 0.6 Mkm^2, we find that gain factors for a mean monthly climatology and fitted semi-annual and annual terms agree mostly to within a few percent (not shown), indicating that a single gain factor is applicable for seasonal variations with the present choice of filter parameters. In addition, we tested the performance of a gain factor based on a mean seasonal signal only (multi-year monthly means in the simulated TWS fields), and find that the error reduction is very similar to the case where the gridded gain factor is based on all monthly TWS anomalies over the 7 years of model data (Fig. 7).

As the GRACE satellites now provide observations of about 9 years of monthly TWS, interannual variations and trends can be resolved. It is therefore important to assess if the scaling described above is applicable beyond the seasonal timescale. The simulated long-term signals over some regions agree well between GRACE and GLDAS-NOAH (e.g.,

US South-East, La Plata), but this is not the case for many other regions (e.g., North-West India, Amazon). Hydrological models often do not capture the full range of inter-annual TWS variations due to missing processes and storage parameterisations, such as groundwater storage or water extraction for irrigation. This has been exploited to extract these unmodeled signals by disaggregating the GRACE observations into water storage components. However, unmodeled TWS signals limit the use of synthetic data to infer a global map of gain-factors that can be applied to actual GRACE observations.

To illustrate this point, we use an example based on *Rodell et al.* [2009], who found significantly different gain factors for the seasonal and secular components of the observed TWS signal in North-West India (Fig. 8a). The seasonal signal (TWS^s) was well correlated over a broad region beyond the averaging region, and therefore not significantly attenuated. In contrast, the interannual component was assumed to be originating from the relatively small averaging region only (based on prior knowledge about the spatial extent of the Indus aquifer), and therefore was significantly attenuated in amplitude. In such a case, the leakage error for the long-period signal (TWS^{lp}) must be treated separately from the seasonal variations (TWS^s) by deriving and applying multiple gain factors:

$$\text{TWS} = k^s\text{TWS}^s + k^{lp}\text{TWS}^{\,lp}. \tag{5}$$

If the spatial extent of the interannual signal TWS^{lp} is known, and if it is only present in GRACE but not in a hydrology model, the gain factor k^{lp} can be estimated by a simple binary distribution of ones over the a priori assumed region, and zeros outside of that region [*Rodell et al.*, 2009]. For the NW-India aquifer and the present choice of filtering parameters, the basin-scale seasonal gain factor is then about 1, whereas the longer period signal requires a gain factor of k^{lp}=3.2.

Had the spatially confined trend signal TWS^{lp} actually been present in GLDAS-NOAH, the reconstruction of the true signal would have revealed that the decomposition of the combined TWS signal into seasonal and long-period anomalies is necessary in order to estimate k^s and k^{lp} from the synthetic data. Without this temporal decomposition, the average gain factor is about 1.7, which would overestimate the seasonal variations, but underestimate the trend (Fig 8b). Only with Eq. 5 can the true signal be accurately reconstructed. Our tests show that this works equally well for the basin-average and grid-point scaling approach (Fig 8c). The observed TWS changes over the NW-Indus aquifer are rather extreme in amplitude, but this case demonstrates that gain factors based on simulated TWS change patterns in some cases may not be used to infer long-period TWS changes of actual GRACE observations; a case-by-case analysis may still be necessary, in particular for smaller regions, such as aquifers or surface reservoirs.

5. Summary and Discussion

GRACE data processing seeks a balance between accuracy and spatial resolution. The level of noise can be reduced by filtering the data, and a variety of different filters have been developed for this purpose, each modifying the data in a specific and characteristic way. However, along with the error reduction comes some loss of signal. In many cases, measurement noise is substantially reduced leaving signal loss as the dominant term in the error budget of the filtered data. This type of error (leakage) can be estimated by applying the filter to a model, and comparing the original and filtered model fields. In this paper, we have described one way of using the information supplied by such an experiment, i.e. a multiplicative gain factor that reduces the differences between the original and filtered model time series in a least squares sense. It allows users of gridded GRACE

TWS observations to average over arbitrary regions of their choice and compare it to other gridded data (e.g., a hydrology model or ground water data set), without having to apply the GRACE filtering process to that data in the spherical-harmonic domain. As detailed above, small spatial scales come at the expense of larger errors, in particular from leakage. Therefore, increasing the size of an averaging region generally reduces errors and uncertainties considerably.

The gain factors derived here are based on simulated TWS variations, and are independent of the actual GRACE observations. Their purpose is to extrapolate the GRACE data to finer spatial scales that are not well resolved by the current GRACE satellites. It is important to keep in mind that while these fine scales are not truly measured by GRACE, our gridded TWS estimates represent these scales to the degree to which a scaling relationship can recover them. This scaling relationship also enables us to quantify leakage and measurement errors based on signal patterns of TWS. The magnitude of the simulated TWS variations is not crucial to the calculation of the gain factors because they aim at restoring relative amplitudes. Thus, the spatial patterns of TWS, which are in part controlled by the large-scale climate patterns of the forcing data (e.g., precipitation and radiation), determine the magnitude and spatial variability of the gain factors. In places where important processes are absent from the model, such as melting of ice sheets and glaciers, or human withdrawal of groundwater, the model-derived gain factors will likely not be accurate. In such cases, a more comprehensive analysis is required to estimate and restore the possible signal loss in the data.

Most of the model-simulated TWS changes occur on the sub-seasonal to seasonal time scales. The derived gain factors therefore are optimized to recover these frequencies, and

may not be suitable for inter-annual or long term signals. A preliminary comparison of trends in GRACE data and trends in hydrological models indicates that it is not advised at this point to produce a global map of long-period gain factors based on these models. For these types of signals, it is recommended that a user carefully examines the model used to estimate filter effects, and if possible augment the model [e.g., Rodell et al.,2009].

The presented method of gridded gain factors and corresponding errors demonstrates that estimating gain factors on a grid-point basis is a viable alternative to the basin-scaling approach that has been used previously. This conclusion is drawn by comparing some prominent river basin averages, both large and small. Thus, providing gridded gain factor and error maps along with gridded GRACE observations over land should enable users to recover attenuated signals from gridded GRACE data, and quantify the appropriate uncertainty that takes measurement and leakage errors into account. The differences between the basin- and grid-point scaling approach generally yield total errors that agree to within 20% over the regions presented here, but we cannot rule out that grid-point gain factors yield worse results than the basin-scaling approach over some user-defined regions. The map of the combined leakage and measurement uncertainty should guide GRACE users in treating regional averages carefully where significant scaling is necessary (Fig. 4), or where the combined error is large (Fig. 6). Mountainous areas in particular are affected due to the short TWS de-correlation length-scales there. Alternative signal restoring methods are possible and may be more or less suitable for a particular region under investigation. For example, mass loss estimates of the Greenland and Antarctic ice sheets from GRACE can be obtained in an iterative procedure [*Chen et al.*, 2009], or by designing optimized special averaging kernels [*Swenson and Wahr*, 2002].

References

Chen, J. L., C. R. Wilson, J. S. Famiglietti, and M. Rodell (2007), Attenuation effect on seasonal basin-scale water storage changes from GRACE time-variable gravity, *J. Geodesy*, *81*, 237–245, doi:10.1007/s00190-006-0104-2.

Chen, J. L., C. R. Wilson, D. Blankenship, and B. D. Tapley (2009), Accelerated antarctic ice loss from satellite gravity measurements, *Nature Geosci*, *2*(12), 859–862.

Famiglietti, J. S., M. Lo, S. L. Ho, J. Bethune, K. J. Anderson, T. H. Syed, S. C. Swenson, C. R. de Linage, and M. Rodell (2011), Satellites measure recent rates of groundwater depletion in california's central valley, *Geophys. Res. Lett.*, *38*(3), L03,403–.

Klees, R., E. A. Zapreeva, H. C. Winsemius, and H. H. G. Savenije (2007), The bias in GRACE estimates of continental water storage variations, *Hydrology and Earth System Sciences*, *11*, 1227–1241.

Landerer, F. W., J. O. Dickey, and A. Gntner (2010), Terrestrial water budget of the eurasian pan-arctic from grace satellite measurements during 2003-2009, *J. Geophys. Res.*, *115*(D23), D23,115–.

Oleson, K. W., et al. (2008), Improvements to the community land model and their impact on the hydrological cycle, *J. Geophys. Res.*, *113*(G1), G01,021–.

Rodell, M., J. S. Famiglietti, J. Chen, S. I. Seneviratne, P. Viterbo, S. Holl, and C. R. Wilson (2004), Basin scale estimates of evapotranspiration using grace and other observations, *Geophys. Res. Lett.*, *31*, 20,504, doi:10.1029/2004GL020873.

Rodell, M., et al. (2004), The global land data assimilation system, *Bull. Amer. Meteor. Soc.*, *85*(3), 381–394.

Rodell, M., I. Velicogna, and J. S. Famiglietti (2009), Satellite-based estimates of groundwater depletion in india, *Nature*, *460*(7258), 999–1002.

Rodell, M., J. S. Famiglietti, and B. R. Scanlon (2010), Realizing the potential of satellite gravimetry for hydrology: Second grace hydrology workshop, *Eos Trans. AGU*, *91*(10), doi:10.1029/2010EO100008.

Schmidt, R., et al. (2006), Grace observations of changes in continental water storage, *Global and Planetary Change*, *50*(1-2), 112 – 126, doi:DOI: 10.1016/j.gloplacha.2004.11.018.

Seo, K.-W., and C. R. Wilson (2005), Simulated estimation of hydrological loads from grace, *Journal of Geodesy*, *78*, 442–456, 10.1007/s00190-004-0410-5.

Swenson, S. (2010), Assessing high-latitude winter precipitation from global precipitation analyses using grace, *Journal of Hydrometeorology*, *11*(2), 405–420, doi: 10.1175/2009JHM1194.1.

Swenson, S., and J. Wahr (2002), Methods for inferring regional surface-mass anomalies from gravity recovery and climate experiment (grace) measurements of time-variable gravity, *J. Geophys. Res.*, *107*(B9), 2193.

Swenson, S., and J. Wahr (2006), Post-processing removal of correlated errors in grace data, *Geophys. Res. Lett.*, *33*(8), L08,402, doi:10.1029/2005GL025285.

Swenson, S., and J. Wahr (2007), Multi-sensor analysis of water storage variations of the caspian sea, *Geophys. Res. Lett.*, *34*(16), L16,401–.

Swenson, S., J. Wahr, and P. C. D. Milly (2003), Estimated accuracies of regional water storage variations inferred from the gravity recovery and climate experiment (GRACE), *Water Resources Research*, *39*, 11–1.

Swenson, S. C., and J. M. Wahr (2011), Estimating signal loss in regularized grace gravity field solutions, *Geophysical Journal International*, *185*(2), 693–702, doi:10.1111/j.1365-246X.2011.04977.x.

Tang, Q., H. Gao, P. Yeh, T. Oki, F. Su, and D. P. Lettenmaier (2010), Dynamics of terrestrial water storage change from satellite and surface observations and modeling, *Journal of Hydrometeorology*, *11*(1), 156–170, doi:10.1175/2009JHM1152.1.

Velicogna, I. (2009), Increasing rates of ice mass loss from the greenland and antarctic ice sheets revealed by grace, *Geophys. Res. Lett.*, *36*(19), L19,503–.

Wahr, J., M. Molenaar, and F. Bryan (1998), Time variability of the earth's gravity field: hydrological and oeanic effects and their possible detection using GRACE, *J. Geophys. Res.*, *103*(B12), 30,205–30,229.

Wahr, J., S. Swenson, and I. Velicogna (2006), Accuracy of GRACE mass estimates, *Geophys. Res. Lett.*, *33*, L06,401, doi:10.1029/2005GL025305.

Figure 1. (top) Root-mean-square variability of filtered GRACE TWS observations (CSR-RL04), and (bottom) corresponding estimates of the measurement error based on *Wahr et al.* [2006]. Note that we have have removed longer than annual TWS signal variations to avoid the inflation of the error from these long-period TWS variations. Units: mm-H_2O.

Figure 2. Root-mean-square variability of observed (GRACE CSR-RL04; left column) and simulated (GLDAS-NOAH; right column) terrestrial water storage: (top row) unfiltered GRACE TWS and GLDAS-NOAH TWS at 1×1 degree resolution; (bottom row) spectrally truncated at degree and order 60, de-striped after *Swenson and Wahr* [2006], and smoothed with a Gaussian of 300 km width. Note the different color range for the unfiltered GRACE data. Units: mm-H_2O.

Figure 3. Basin-mean water storage for the Columbia River basin: (a) original and filtered GLDAS-NOAH; (b) original *vs* the scaled basin-mean TWS (basin-scaled and pixel-scaled version) GLDAS-NOAH; (c) original GLDAS-NOAH TWS compared to scaled GRACE-TWS (CSR-RL04). Units: mm-H_2O.

Figure 4.   Gain factors for GLDAS-NOAH monthly TWS variations derived by least-square fitting each filtered grid-point (at 1×1 degree resolution) time series to the unfiltered time series (see Eq. 1).

Figure 5.   Correlation between filtered and unfiltered time series for monthly TWS variations from GLDAS-NOAH.

Figure 6.   GRACE TWS error maps. (top) GRACE-measurement errors are based on the method of *Wahr et al.* [2006], and are scaled with the grid-point gain factors from Fig. 4; (middle) the residual leakage error estimate, scaled by the ratio of the RMS variability of GRACE and GLDAS-NOAH; (bottom) total errors from combining leakage and measurement errors in quadrature. Note that although the errors are spatially correlated, averaging over a region will reduce the grid-point errors, e.g., for the Amazon basin the total error is about 11.3 mm-H_2O (Tab. 1). Units: [mm-H2O].

.

Figure 7.   Histogram of RMS differences between unfiltered GLDAS monthly mean TWS and the filtered GLDAS amplitudes (blue line), and the filtered GLDAS amplitudes scaled with a gain factor based on all monthly anomalies (black line), and scaled with a gain factor based on a mean seasonal signal only (red line).

Figure 8.   (a) NW-India Indus Aquifer averaging region (inside polygon) and averaging kernel after spectral truncation of the exact mask at degree l=60; (b) Mean TWS over the Aquifer based on GLDAS-NOAH plus an added trend (-4 cm/yr) for the unfiltered, filtered, and reconstructed data using only one gain factor as in Eq. 1; (c) as (b), but decomposing the signal into seasonal and long-period components and deriving separate gain factors for each using Eq. 5. See *Rodell et al.* [2009] for a more detailed discussion of TWS in this region.

Table 1.   Gain factors, leakage, measurement, and combined errors for unfiltered and

filtered TWS variations for various drainage basins (ordered by decreasing size). The gain

factors k_b are unitless, all errors are in units of mm of equivalent water height.

Basin	k_b	Error (Leakage)			Error (Measurement)		Error (Combined)		RMS ratio
		$(E_b^l)^a$	$(E_{b,k_b}^l)^b$	$(E_g^l)^c$	$(E_b^m)^d$	$(E_g^m)^e$	$(E_b^t)^f$	$(E_g^t)^g$	(GRACE/GLDAS)
Amazon	1.02	7.6	7.1	7.0	9.2	8.8	11.5	11.2	1.8
Zaire	1.14	7.8	4.9	5.5	12.2	11.3	11.8	12.6	1.1
Mississippi	1.00	4.7	4.7	5.1	9.6	6.4	10.7	8.2	1.2
Ob	1.00	2.0	2.0	3.6	9.3	6.1	9.5	7.1	1.1
Parana	1.18	12.3	7.7	6.3	12.6	12.3	13.1	13.8	1.1
Yenisei	1.03	3.8	3.5	5.0	9.6	6.8	9.9	8.4	1.2
Lena	1.10	4.7	2.5	5.3	10.3	7.9	9.6	9.5	1.3
Niger	1.06	5.4	4.1	5.9	11.5	10.5	11.6	12.0	1.4
Tamanrasett	0.62	8.6	6.8	5.0	7.3	6.1	13.6	7.9	3.2
ChangJiang	1.03	7.6	7.5	11.8	10.9	11.8	12.9	16.6	2.1
Missouri	0.78	14.0	8.7	6.9	8.2	6.2	13.6	9.3	1.5
Amur	1.17	5.8	3.2	6.6	12.4	10.1	11.0	12.1	1.1
Mackenzie	0.97	4.6	4.3	7.4	9.8	7.5	11.0	10.5	1.1
Ganges	1.11	13.4	8.5	12.8	12.4	11.5	14.0	17.2	1.5
Volga	1.08	4.8	2.2	3.9	11.3	8.4	10.7	9.2	0.9
Zambezi	1.11	14.1	7.0	7.6	13.3	16.9	13.9	18.5	1.2
Indus	1.26	25.4	23.5	17.2	15.4	12.6	26.5	21.3	2.1
Orinoco	1.23	39.9	27.0	20.7	16.4	18.3	30.1	27.6	2.7
Murray	1.34	18.3	16.5	8.1	16.9	15.3	20.7	17.3	2.4
Yukon	1.23	20.8	12.5	16.4	13.3	11.5	16.6	20.1	1.5
Colorado(Arizona)	1.01	9.3	9.3	6.7	12.6	10.9	15.5	12.8	1.7
Danube	1.15	14.6	11.0	9.1	14.1	11.6	16.5	14.8	1.1
Mekong	1.51	55.9	19.8	18.1	18.9	23.1	23.5	29.4	1.9
Columbia	1.44	31.9	13.5	15.6	17.5	15.5	18.2	21.9	1.6
Okavango	1.10	8.6	6.9	6.9	15.1	18.5	15.4	19.7	0.9
Kolyma	1.15	9.9	7.1	8.5	13.6	12.0	13.8	14.7	1.2
Arkansas	0.99	19.4	19.4	15.3	12.7	12.1	23.3	19.4	1.3
Irrawaddy	1.21	83.5	79.2	39.2	18.4	21.8	80.6	44.8	1.9
Godavari	1.31	36.0	13.9	14.6	19.8	27.8	20.5	31.4	1.3
Huai	1.47	28.8	20.7	17.1	20.8	22.7	25.1	28.4	1.4
Fraser	1.56	53.7	26.3	30.6	20.0	21.1	29.2	37.2	1.6
Anadyr	1.67	39.1	25.0	18.7	21.9	23.8	28.2	30.2	1.6
Chubut	1.98	34.5	22.2	20.5	26.3	28.8	25.9	35.4	1.6
Rufiji	1.23	31.2	23.4	27.6	19.0	26.5	28.1	38.3	1.5
Taz	1.16	17.0	11.1	11.1	14.2	15.3	16.5	19.0	1.1
Sacramento-SanJoaquin	2.90	95.2	47.0	27.7	39.6	39.1	48.9	48.0	2.0
Pyasina	1.47	35.8	17.3	13.0	18.9	22.3	21.6	25.8	1.3
Essequibo	1.22	49.8	42.7	36.3	19.5	26.6	45.5	45.0	2.0
Koksoak	1.45	23.9	14.4	9.7	18.6	21.1	19.2	23.2	0.9
Loire	1.44	21.6	10.7	13.5	19.7	21.7	17.4	25.5	0.8
Narmada	1.29	36.1	16.4	16.5	19.2	25.0	22.1	29.9	1.2
Flinders	1.28	28.0	24.1	15.1	21.0	31.9	29.2	35.3	1.2
Cunene	1.37	27.4	20.0	13.9	22.7	34.7	26.0	37.4	0.8
Douro	2.14	46.8	17.0	17.5	30.3	35.7	22.2	39.7	1.0
Barito	2.46	94.4	36.9	33.5	44.0	70.8	41.0	78.4	2.4
Gambia	1.49	45.5	23.4	24.4	24.3	39.7	28.5	46.6	1.3

[a] Leakage error based on GLDAS

[b] basin-mean residual leakage (k_b applied)

[c] grid-based GLDAS leakage error

[a,b,c] (adjusted for RMS-ratio GRACE/GLDAS)

[d] basin-mean GRACE measurement error [*Wahr et al.*, 2006]

[e] grid-based GRACE measurement error

[d,e] (adjusted for basin (d) and gridded (e) gain factors)

[f] Total error from basin-means (b & d)

[g] Total error from basin-means (c & e)

GRACE RMS: CSR–RL04sw06;sw06,300km,01/2003–08/2010

histogram of grid-point RMS values (area weighted)

Kernel: Indus Plain River aquifer; trunc=60, GW=0, nds